



Dyer & Butler



Site clearance & enabling works



January 2017



29 weeks

We were contracted to clear site of block paving, fencing and cycle stands to allow for the jacking and demolition of existing bridge piers.

We then put in a retaining H beam wall to allow the excavation of new pier foundations.

We undertook the concrete and associated works to the foundations, vertical pier and jacking plinth to 2nr new piers works being undertaken concurrently.

Following the piers we reinstated the site and installed new fencing.



Universal Group

Unit 4, Nunn Close,
Huthwaite, Sutton In Ashfield,
Nottinghamshire, NG17 2HW

Reg03728536, VAT990830888