



J Murphy & Sons



Install of hollow bar anchors



June 2016



10 weeks

We were contracted by JP Murphy & Sons to install 120nr Anchors to strengthen an existing retaining wall as part of the Gospel Oak to Barking Track Lowering Scheme.

The majority of the anchors (R38, upto 14m long, 190mm annulus) were inside the tunnel of an operational railway; We therefore had to overcome the restricted access conditions inside the tunnel as well as limited working time during OROR possessions. This was accomplished using an RRV, with self contained grout unit and a modified TEI Mast.

Despite all of the challenges, we handed the scheme over snag free on time, below budget and to the clients complete satisfaction.



Universal Group

Unit 4, Nunn Close,
Huthwaite, Sutton In Ashfield,
Nottinghamshire, NG17 2HW

Reg03728536, VAT990830888