



AMCO



Bridgeworks



October 2016



16 weeks

We were contracted by AMCO to undertake the removal of the existing bridge and the construction & installation of the new bridge.

The scope of these works included :

Works on site :-

Installation of 8nr 450mm augered piles for new abutment.

Brickwork repairs to abutments and wing walls.

The single sided wall shutters for the abutment wall.

Kentledge block for the RMD single sided wall shutters.

S&T cable bridge foundations.

Access through hedgerow and placement of gas main/ ditch protection access bridge.

Outrigger foundations for the 130T crane.

Site Compound Works :-

Foundation for the trestle support

Falsework for the bridge deck installed by us

Falsework foundation installation and ply to bridge deck

Install PC sills and beams on trestles from scaffold

Install reinforcement and cast the bridge deck

Other Items :-

Engineering

Earthworks to compound

24/7 working

Fencing



Universal Group

Unit 4, Nunn Close,
Huthwaite, Sutton In Ashfield,
Nottinghamshire, NG17 2HW

Reg03728536, VAT990830888